BUILDINGS DIVISION.

Notification dated 7th June 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 26th June 1937, up to 2 P.M., for the extension of the Government Fort High School, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Buildings Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees eight hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extension of the Government Fort High School, Bangalore in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for extension of the Government High School, Bangalore City at Fort.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation for foundation and the same to the basement with watering and tamping	C.yds.	0 3 6	165	
2	Burnt stone jelly concrete (1 : 2) in lime mortar including tamping, etc.	C.ft.	0 3 6	1,242	
3	Size stone in lime mortar for foundation and basement including quoin dressing ..	„	0 4 6	2,732	
4	Burnt brick in lime mortar superstructure ground floor	„	0 4 0	2,537	
5	Burnt brick in lime mortar superstructure First floor	„	0 4 6	3,789	
6	Burnt stone slabs 6″ thick, two line dressed to exposed faces and one line dressed to other faces and fixed in lime mortar	S.ft.	0 7 0	223	
7	Do 6″ thick one line dressed at top and two line dressed to other faces and fixed in lime mortar	„	0 6 0	847	
8	Providing and fixing cut stone pillars with base and capital two line dressed all over 12′ height 1½′ square base and capital and 1′ square shaft as per approved design including cement pointing	Each	30 0 0	14	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
9	Providing and fixing T.W. windows fully panelled 4″×3″ frame and 1″ shutters with iron fittings including semi-circular fan lights fully glazed as per existing ones	S.ft.	2 0 0	789	
10	Providing and fixing T.W. doors fully panelled frame 4″×5″ with 1¼′ shutters with iron fitting including semi-circular fan lights at top as per existing ones	,,	1 12 0	372	
11	Brick on edge (pucca) terrace with 3″ brick concrete and two courses of flat tiles on top including top and bottom plastering ..	Sqr.	32 0 0	39·53	
12	Roofing with 1st class Mangalore tiles on teak wood reepers including nailing, etc., complete, reepers 2″×1″	,,	24 0 0	35·08	
13	Ridge tiles (Mangalore) set in mortar including cement pointing	R.ft.	0 7 0	150	
14	Mysore Teakwood wrought and put up with two coats of wood oiling and tarring the ends of rafters	C.ft.	4 8 0	385·8	
15	Rolled steel joists Tata's tested with coat of anti corrosive paint including hoisting and fixing with necessary rods and bolts ..	Cwts.	11 0 0	99·6	
16	Burnt brick in mortar Arch work over doors and windows	C.ft.	0 6 0	538	
17	Partition wall with burnt brick in mortar ex-metal at every 4th course including cement mortar plastering, etc.	S.ft.	0 8 0	1,311	
18	Providing and fixing R.C. perforated ventilators as per approved design	,,	0 8 0	180	
19	Flooring with burnt stone slabs 3″ to 4″ thick 3″ stone jelly concrete in lime mortar including cement pointing and one line dressed at top.	on Sqr.	30 0 0	11.30	
20	Flooring with 1st class Mangalore tiles on cement mortar bed and cement pointing, etc., complete	,,	16 0 0	33.0	
21	Burnt brick in mortar cornice 9″×9″ ornamental as per approved design including plastering white washing, etc., complete	R.ft.	0 10 0	307	
22	Burnt brick in mortar parapet wall 3′ height over verandah 'ballustrated' as per approved design	,,	2 0 0	66	
23	Burnt brick in mortar parapet wall 2′ height including plastering, etc., complete as per approved design	,,	1 8 0	86	
24	Zinc sheet valleys over T. W. planks ½″ thick 3′ wide with necessary cement plastering and cement bands, etc., complete	,,	0 14 0	86	
25	Cement pointing, with cutting lines ..	Sqr.	3 4 0	4.30	
26	Painting to doors and windows with Government Factory silicate paint	,,	3 8 0	20.31	
27	Chunam plastering, 2 coats	Sqr.	3 4 0	104.54	
28	Mortar bands 4½″ thick over roof including plastering, etc., complete	R.ft.	0 2 6	74	
29	Providing and fixing ornamental rain water spouts as per approved design	No.	2 0 0	6	
30	Eave board 9″ deep 1″ thick T. W. ornamental including fixing as per approved design ..	R.ft.	0 10 0	263	
31	White and colour washing 2 coats	Sqr.	0 4 6	104.54	

B. R. GARUDACHAR,
Executive Engineer.